

Exhibit A

Estimate

JRH Construction, LLC
PO Box 1661
Oregon City, OR 97045



GENERAL CONTRACTOR

NEW CONSTRUCTION

REMODELING

Name/Address
Oregon city PD 320 Warner Milne Rd. Oregon City OR 97045

Date	Estimate No.	Project
07/20/15	2014-9	

Item	Description	Quantity	Cost	Total
Fencing	<p>Supply Labor and materials for the following.</p> <p>550 LF of 6' tall vinyl coated chain link fence color to be black. (2) 12' swing gates for 24' opening.</p> <p>109'x6' tall iron fence top rail 1"x2" post to be 1 1/2" sq and pickets to be 3/4" powder coated.</p> <p>One wall gate to be 45"x72" powder coated with dead bolt passage.</p> <p>Build and install one iron powder coated driveway gate 6' high from blacktop 24' 8" long overall.</p> <p>Opening would be 16' min. wide. 2x4 .120 wall tube frame with 3/4"sq pickets. One Elite SL-3000 slide gate operator two safety loops for automatic close mode. One Omron photo safety.</p> <p>Saw cut for gate, iron fencing and power ditch to gate opener patch back with asphalt or concrete.</p> <p>75 transmitters ea. additional with be \$15.</p> <p>Anytime for rock roots or debris will be charged at \$75.00 per man hr.</p>		57,325.00	57,325.00
Estimate good for 30 Days.			Total	\$57,325.00